

The MK 100/110 mobile construction crane. Fast, powerful and reliable. Telescopic jib - Reach up to 52.0 m Super-raised working angle: 68,0 m hook height at 37,2 m working radius One-person assembly in 17 minutes * **Technical data** Max. lifting capacity 8,000 kg Lifting capacity at jib head 2,300 / 1,800 kg Working radius 44.0 / 52.0 m Hook heights Tower retracted 25.0 m 33.0 m Tower extended 15° raised working angle 45.7 m 30° raised working angle 58.0 m 45° super-raised working angle 68.0 m Total weight 60.0 t


10 x 8 x 10

Drive / Steering

LIEBHERR

* from the supported position





Printed in Germany BK LBC-680-11.09-gb This information is supplied without liability. Subject to technical modifications.

Liebherr-Werk Biberach GmbH

Postfach 1663, D-88396 Biberach an der Riß

+49 (0)7351 41-0, Fax +49 (0)7351 41-22 25

www.liebherr.com. E-Mail: info.lbc@liebherr.com