



### **STINGER 3470** | Boom Truck Crane



#### **FEATURES**

- 34,000 lb (15 422 kg) maximum lifting capacity
- ▶ 80' (24.38 m) maximum sheave height
- ▶ 120' (36.57 m) maximum sheave height with 24-40' (7.31-12.19 m) jib
- 27-70' (82.30-21.34 m) three-section full power fully synchronized boom
- Exclusive color coded boom and load charts
- Easy-to-install optional 24' (7.31 m) one stage or 24-40' (7.31-12.19 m) two stage telescoping jib, man baskets or work platform increase job capacities

- Electronic Load Moment Indicator and anti-two-block device standard
- Externally located planetary rotation drive for easy accessibility for maintenance
- 2-speed planetary winch has 10,500 lb (4 703 kg) maximum permissible 1 part line, 37,000 lb (16 782 kg) breaking strength, 186 ft/min (57 m/min) maximum line speed
- Dual control station with direct mechanically controlled hydraulic system
- 70 gal (266 L) capacity hydraulic tank






## **BOOM TRUCK CRANE** STINGER 3470

LOAI	) RAT	INGS		is not o	onsistent wil	this specifical h the machine	chart and ma	y be subject to	change	i oi data			
									TS				
воом													AREA OF OPERATIO
PERATING RADIUS (FT)	BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	IN SHADED AREA WITHOUT OPTIONAL FRONT STABILIZER
5	77	34,000*	-										
10	66	21,100*	71	17,100*	75	16,000*	78	15,700*					
15	54	15,100*	62	14,000*	68	12,100*	72	11,100*	75	10,800*	77	9,600*	
20	39	11,100*	51	10,100*	61	9,100*	66	8,600*	71	8,200*	73	7,300	Frank Toll
25	17	7,900*	40	7,700*	53	7,100*	61	6,900°	66	6,600*	69	5,900*	
30			23	6,500*	44	6,100*	54	5,600*	60	5,300*	64	4,900*	<b>₩₩₩</b>
35					33	4,800*	47	4,700*	54	4,600*	60	4,150*	
40		TRUCTURAL ST ARE INDICATED			16	3,500*	38	4,100*	48	3,900*	55	3,550*	
45							27	3,250*	41	3,200*	49	3,050*	Deductions from rate
50							9	2,950°	33	2,800*	44	2.650*	loads for load handling devices BT
55									23	2,500*	37	2 3501	
60				and the state of							29	1,900	Overhaul Ball 125 lbs
65											19	1,700*	1 Sheave Load Block 200 lbs

JIB CAPACITII	ES FOR A	ALL BO	OM LE	NGTHS	VERIFY OPER	RATIONAL MODE	SETTING ON L	.MI DISPLAY BE	FORE LIFTING	WITH JIB
Loaded Boom Angle	35°	40°	45°	50°	55°	60°	65°	70°	75°	80°
Retracted 24 ft Jib	700	825	1,000	1,150	1,340	1,600	1,900	2,300	3,100	4,160
Extended 40 ft Jib	520	580	650	730	810	930	1,080	1,400	1,810	2,260



#### **GENERAL NOTES**

- 1. The operator must read and understand the Owner's Manual before operating this crane,
- 2. Positioning or operation of crane beyond areas shown on this chart is not intended or approved except where
- Loaded boom angles at specified boom lengths give only an approximation of the operating radius. The boom angle before loading should be greater to account for deflections. Do not exceed the operating radius for rated loads.
- 4. Use rating of next longer boom for boom lengths not shown. Use rating of next greater radius for load radii not shown. 5. Boom must be fully retracted when jib is erected before lowering below minimum angle. Retracted jib has no lifting
- capacity below a 50° boom angle.
- 6. Use rating of next lower boom angle for boom angles not shown on jib load rating chart
- 7. Lifting off the main boom point while the swing around jib is erected is not intended or approved.8. Do not lower boom into this area, as hydraulic pressure will not allow raising the boom without retracting boom first.
- 9. Crane load ratings on outriggers are based on freely suspended loads with the machine leveled and standing on a firm uniform supporting surface. No attempt shall be made to move a load horizontally on the ground in any direction.
- 10. Practical working loads depend on supporting surface, wind and other factors affecting stability such as hazardous surroundings, experience of personnel, and proper handling, must all be taken into account by the operator.
- 11. The maximum load which may be telescoped is limited by hydraulic pressure, boom angle, and boom lubrication. It is safe to attempt to telescope any load within the limits of the load rating chart.

#### 1. Deductions must be made from rated loads for stowed jib, optional attachments, hooks and loadblocks (see deduction chart). Weights of slings and other load handling devices shall be considered a part of the load.

- 2. Crane load ratings with outriggers are based on outriggers and stabilizers extended and set with all load removed from the carrier wheels.
- 3. Load ratings do not exceed 85% of tipping load.

#### DEFINITIONS

- 1. Operating radius is the horizontal distance from the axis of rotation to the center of the vertical hoist line or load hook with load suspended.
- 2, Loaded boom angle as shown in the Load Ratings Chart is the included angle between the horizontal and longitudinal axes of the boom base after lifting rated load at rated radius






### **BOOM TRUCK CRANE** STINGER 3470

				CAUTI is not	eorotometvitt	T CIG Indentific	chart and may	ou vabject (U	rs rs				
HOOM									IS				
OPERATING RADIUS (FT)	BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	LOADED BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	BOOM ANGLE (DEG)	LOAD RATING (LB)	AREA OF OPERATION 360° Full Capacity Area of
5	77	34,000*											Operation
10	66	21,100*	71	17,100*	75	16,000*	78	15,700*					
15	54	15,100*	62	14,000*	68	12,100°	72	11,100*	75	10,800*	77	9,600*	< ff€ >
20	39	11,100*	51	10,100*	61	9,100*	66	8,600°	71	8,200*	73	7,3001	
25	17	7,900*	40	7,700*	53	7,100*	61	6,900*	66	6,600*	69	5,900"	
30			23	6,500*	44	6,100*	54	5,600°	60	5,300	64	4,900*	1 20
35	NOTE O	TOLIOTIDAL C	TOTAL DAT	MOD IN	33	4,800*	47	4,700*	54	4,600*	60	4,150*	
40		TRUCTURAL S' ARE INDICATED			16	3,500°	38	4,100*	48	3,900*	55	3,550*	
45	1						27	3,250*	41	3,200*	49	3,090*	
50							9	2,950*	33	2,800*	44	2,650*	
55									23	2,500*	37	2,350*	Deductions from rate loads for load handling
60											29	1,900*	devices RM
65											1.9	1,700*	Overhaul Balí 125 lbs

JIB CAPACITII	ES FOR A	ALL BO	OM LEI	NGTHS	VERIFY OPER	ATIONAL MODE	SETTING ON L	.MI DISPLAY BE	FORE LIFTING	WITH JIB
Loaded Boom Angle	35°	40°	45°	50°	55°	60°	65°	70°	75°	80°
Retracted 24 ft Jib	700	825	1,000	1,150	1,340	1,600	1,900	2,300	3,100	4,160
Extended 40 ft Jib	520	580	650	730	810	930	1,080	1,400	1,810	2,260



#### **GENERAL NOTES**

- The operator must read and understand the Owner's Manual before operating this crane.
   Positioning or operation of crane beyond areas shown on this chart is not intended or approved except where
- specified in Owner's Manual,
- appearance in corner a manual.

  3. Loaded boom angles at specified boom lengths give only an approximation of the operating radius. The boom angle before loading should be greater to account for deflections. Do not exceed the operating radius for rated loads.
- 4. Use rating of next longer boom for boom lengths not shown. Use rating of next greater radius for load radii not shown. 5. Boom must be fully retracted when Jib is erected before lowering below minimum angle, Retracted jib has no lifting
- 6. Use rating of next lower boom angle for boom angles not shown on Jib load rating chart.
- 7. Lifting off the main boom point while the swing around jib is erected is not intended or approved.
   8. Do not lower boom into this area, as hydraulic pressure will not allow raising the boom without retracting boom first.
- Crane load ratings on outriggers are based on freely suspended loads with the machine leveled and standing on a firm uniform supporting surface. No attempt shall be made to move a load horizontally on the ground in any direction.
- 10. Practical working loads depend on supporting surface, wind and other factors affecting stability such as hazardous surroundings, experience of personnel, and proper handling, must all be taken into account by the operator.
- 11. The maximum load which may be telescoped is limited by hydraulic pressure, boom angle, and boom lubrication. It is safe to attempt to telescope any load within the limits of the load rating chart.
- Deductions must be made from rated loads for stowed jib, optional attachments, hooks and loadblocks (see deduction charl). Weights of slings and other load handling devices shall be considered a part of the load.
- Crane load ratings with outriggers are based on outriggers and stabilizers extended and set with all load removed from the carrier wheels.
- 3. Load ratings do not exceed 85% of tipping load.

#### DEFINITIONS

- 1. Operating radius is the horizontal distance from the axis of rotation to the center of the vertical hoist line or load hook with load suspended.

  2. Loaded boom angle as shown in the Load Ratings Chart is the Included angle between the hortzontal and longitudinal
- axes of the boom base after lifting rated load at rated radius.





### **BOOM TRUCK CRANE** STINGER 3470

#### **BT MODEL**

WINCH DATA								
		1 Part Line	2 Part Line	3 Part Line	4 Part Line			
		Distribut.	20 00 00 00 00 00 00 00 00 00 00 00 00 0	100 mm				
Winch	Cable Supplied	Lift and Max Speed	Lift and Max Speed	Lift and Max Speed	Lift and Max Speed			
Standard Stationary	9/16" Diam IWRC XXIP	10,500 lb 186 fpm	21,000 lb 93 fmp	31,500 lb 62 fpm	34,000 lb 45.5 fpm			
Winch	9/16" Diam Rotation Resistant	6,720 lb 186 fpm	13,440 lb 93 fpm	20,160 lb 56.7 fpm	26,880 lb 45.5 fpm			

#### **BLOCK TYPE** Overhaul Ball 6.25 ton (5.7 mt) 1 Sheave Block 17.5 ton (15.9 mt)


#### CAUTION A

Overload and anti-two-block systems must be in good operating condition before operating crane. Refer to Owners Manual.

Keep at least 3 wraps of loadline on drum at all times.

Use only 9/16" diameter cable with 37,000 lb. breaking strength on this machine.

#### **2 MOUNTING CONFIGURATIONS**



# 4.65" [0.37 m] 03,83°

#### **CARRIER PROVIDED BY TEREX**

STINGER BT3470 - Behind Cab Mounting Configuration

 Manufacturer Ford F-750 4 x 2 Chassis Standard Engine Caterpillar C-7 7.2 L I-6 Standard Horsepower 210 hp @ 2,500 rpm Standard Torque 605 lb. Ft. @ 1,440 rpm Full Tank Capacity 45 gal (170 L) Standard Transmission Spicer FS066-7B Speed Standard Transmission Manual 7-speed Max Speed Standard Transmission 74 mph (118.4 km/h) Max Gradeability 17.7% in 1st Standard Transmission 15.8% in Rev Optional Transmission Allison

 Speed Optional Transmission Automatic 5-speed Max Speed Optional Transmission 74 mph (118.4 km/h) Max Gradeability 21.1% in 1st Optional Transmission 30.5% in Rev Gross Vehicle Weight Rating 33,000 lb (14 969 kg) Front Axle Weight Rating 12,000 lb (5 443 kg) Rear Axle Weight Rating 21,000 lb (9 525 kg)

Front Tires 22.5" x 8.5" 11R22.5 G Goodyear G159 Rear Tires Brakes Air, Hydraulic Anti-Lock System

22.5" x 7.5" 11R22.5 G Goodyear G167A Exhaust Position Horizontal Left Side

#### **INCLUDED OPTIONS**

- ▶ Fuel tank (45 gal)-175 L
- Power Steering
- Electric Horn
- ▶ Factory A/C
- Power Port (Cigar lighter)
- AM/FM Radio w/ Clock
- Dual West Coast Stainless Rear View Mirrors
- Standard Factory Warranty

#### **CHASSIS RECOMMENDATIONS**

STINGER BT3470 - Behind Cab Mounting Configuration

 Combined Axle Weight Rating 33,000 lb (14 969 kg) Front Axle Weight Rating 12,000 lb (5 443 kg) Rear Axle Weight Rating 21,000 lb (9 525 kg) Wheel base 242" (6.15 m) 168" (4.27 m) Cab to Axle 96" (2.44 m) Afterframe Frame Section Modulus 16.98 in<sup>3</sup> (278 cm<sup>3</sup>) 1,400,000 in/lb (16 130 kg/m) RBM per Frame Rail

 Frame Height (Unloaded) 40" (7.62 m) Exhaust Position Horizontal Left Side





# STINGER 3470

#### RM MODEL

WINCH DATA							
		1 Part Line	2 Part Line	3 Part Line	4 Part Line		
		The state of the s	STATE UNITS	AST STATE OF			
Winch	Cable Supplied	Lift and Max Speed	Lift and Max Speed	Lift and Max Speed	Lift and Max Speed		
Standard Stationary	9/16" Diam IWRC XXIP	10,500 lb 186 fpm	21,000 lb 93 fmp	31,500 lb 62 fpm	34,000 lb 45.5 fpm		
Winch					6,880 lb 5.5 fpm		


BLOCK TYPE							
Overhaul Ball	6.25 ton (5.7 mt)						
1 Sheave Block	17.5 ton (15.9 mt)						

#### CAUTION A

Overload and anti-two-block systems must be in good operating condition before operating crane. Refer to Owners Manual.

Keep at least 3 wraps of loadline on drum at all times.

Use only 9/16" diameter cable with 33,600 lb. breaking strength on this machine.



#### **CARRIER PROVIDED BY TEREX**

STINGER RM3470 - Rear Mount Configuration

Sterling LT7501 6 x 4 (60 000) Manufacturer Standard Engine Caterpillar C-7 7.2 L I-6 300 hp @ 1,440 rpm Standard Horsepower Standard Torque 860 lb. Ft. @ 1,500 rpm Full Tank Capacity 120 gal (454 L) Standard Transmission Eaton Fuller RT-8908LL Speed Standard Transmission Manual 10-speed Max Speed Standard Transmission 74 mph (120 km/h)

Max Gradeability 54%

Standard Transmission

Optional Transmission
 Allison

Speed Optional Transmission
 Max Speed Optional Transmission
 74 mph (120 km/h)


Max Gradeability 17%

Optional Transmission

Gross Vehicle Weight (without crane)
 Front Axle Weight Rating (without crane)
 Rear Axle Weight Rating (without crane)
 40,000 lb (18 144 kg)

Front Tires
 Rear Tires
 Brakes
 425/65R 22.5 Michelin XZY (20 ply)
 11R 22.5 Michelin XDE M/S (14 ply)
 Brakes
 Air, Hydraulic Anti-Lock System

▶ Exhaust Position Horizontal Left Side



#### **INCLUDED OPTIONS**

- Dual Fuel Tanks (120 gal-454 L)
- Power Steering
- Electric Horn
- Factory A/C
- Power Port (Cigar lighter)
- ▶ AM/FM Radio w/ Clock
- Dual West Coast Stainless Rear View Mirrors
- Standard Factory Warranty

#### **CHASSIS RECOMMENDATIONS**

STINGER RM3470 - Rear Mount Configuration

 ▶ Combined Axle Weight Rating
 60,000 lb (27 210 kg)

 ▶ Front Axle Weight Rating
 20,000 lb (9 067 kg)

 ▶ Rear Axle Weight Rating
 40,000 lb (18 144 kg)

 ▶ Wheat Rear
 20,000 lb (27 210 kg)

Wheel Base 261" (6.62 m)
 Cab to Axle 192" (4.87 m)
 Afterframe 114" (2.89 m)
 Frame Section Modulus 30.00 in³ (4.91 cm³)

RBM per Frame Rail 1,800,000 in/lb (16 130 kg/m)

► Frame Height (Unloaded) 40" (7.62 m)

► Exhaust Position Horizontal Left Side






# STINGER 3470

#### BT MODEL

#### **SPECIFICATIONS**



#### **BOOM**

• 27-70' (82.30-21.34 m) three-section full power fully synchronized boom. Patented keel boom design utilizes a keel shaped base plate combined with a deep, four plate boom section to optimize strength / rigidity-to-height ratio. Exclusive, patented color-coded boom and load charts allow the operator to easily determine boom extension, boom angle and load capacity. Maximum tip height with three-section 27-70' (82.30-21.34 m) boom is 80' (24.38 m). Maximum tip height with optional two-stage 24-40' (7.31-12.19 m) jib is 120' (36.57 m).

#### **WINCH**

 Hydraulic winch with gear motor and planetary reduction gearing provides 2-speed operation. First layer rope pull is 11,400 lb (5 170 kg). Wire rope size is 9/16" (14 mm) with 37,000 lb (16 782 kg) breaking strength.

#### **OPERATING SPEEDS**

 Mainframe / turret assembly planetary gear rotation provides 180° rotation (370° with optional front bumper outrigger). Swing rotation is 55 seconds. Boom up/down is 25/16 seconds and boom extend/retract is 61/29 seconds.

#### **HYDRAULICS**

 Three-section pump allows the operator to perform simultaneous crane operations (winch, boom and swing). Capacities are 32, 17 and 8 gpm (122, 64 and 30 L/m). Hydraulic tank capacity is 70 gal (265 L).

#### CONTROLS

Fully proportional, excellent metering characteristics for precise boom movements. Independent outrigger controls allow the crane to be stable and level in rigorous working conditions. Load Moment Indication System has audio alarm and functional shut down when operator encounters an overload situation.

#### **OUTRIGGERS**

- Front outriggers are Link-Type. The maximum width over main outrigger pad is 20' 5" (6.23 m), main outrigger spread at maximum ground penetration is 20' (6.10 m).
- Rear outriggers are A-Frame type. The maximum width over auxiliary outrigger pads is 10' 2" (3.09 m).

#### SUBFRAME

 Single fabricated, closed-box style subframe yields greater strength and rigidity. Wheelbase for standard truck crane mounting configuration is 242" (6.15 m).

#### **OPTIONS AND ACCESSORIES**

- ▶ Single and two-stage jibs
- Multi-part load blocks
- Main winch with 2 speed motor
- Auxiliary winch
- Rotation-resistant load line
- Heavy duty wood flatbeds
- Extra heavy duty wood flatbeds
- Extra heavy duty steel flatbeds
- Radio remote controls
- One-man or two-man baskets

- Self-leveling work platform
- Winch drum tensioner
- Continuous rotation
- Oil cooler
- Single front bumper outrigger (required for 370° or continuous rotation)
- Hydraulic hose reel
- Hydraulic auxiliary tool circuit
- ▶ Tool Box





# STINGER 3470

#### RM MODEL

#### **SPECIFICATIONS**



#### **BOOM**

• 27-70' (82.30-21.34 m) three-section full power fully synchronized boom. Patented keel boom design utilizes a keel shaped base plate combined with a deep, four plate boom section to optimize strength / rigidity-to-height ratio. Exclusive, patented color-coded boom and load charts allow the operator to easily determine boom extension, boom angle and load capacity. Maximum tip height with three-section 27-70' (82.30-21.34 m) boom is 80' (24.38 m). Maximum tip height with optional two-stage 24-40' (7.31-12.19 m) jib is 120' (36.57 m).

#### **WINCH**

 Hydraulic winch with gear motor and planetary reduction gearing provides 2-speed operation. First layer rope pull is 11,400 lb (5 170 kg). Wire rope size is 9/16" (14 mm) with 33,600 lb (15 240 kg) breaking strength.

#### **OPERATING SPEEDS**

 Mainframe / turret assembly planetary gear rotation provides 180° rotation (370° with optional front bumper outrigger). Swing rotation is 55 seconds. Boom up/down is 25/16 seconds and boom extend/retract is 61/29 seconds.

#### **HYDRAULICS**

 Three-section pump allows the operator to perform simultaneous crane operations (winch, boom and swing). Capacities are 32, 17 and 8 gpm (122, 64 and 30 L/m). Hydraulic tank capacity is 70 gal (265 L).

#### CONTROLS

Fully proportional, excellent metering characteristics for precise boom movements. Independent outrigger controls allow the crane to be stable and level in rigorous working conditions. Load Moment Indication System has audio alarm and functional shut down when operator encounters an overload situation.

#### **OUTRIGGERS**

- Rear outriggers are Link-Type. The maximum width over main outrigger pad is 20' 5" (6.23 m), main outrigger spread at maximum ground penetration is 20' (6.10 m).
- Front outriggers are Out and Down type. The maximum width over auxiliary outrigger pads is 17' 6" (5.34 m).

#### **SUBFRAME**

 Single fabricated, closed-box style subframe yields greater strength and rigidity. Wheelbase for standard truck crane mounting configuration is 261" (6.63 m).

#### **OPTIONS AND ACCESSORIES**

- Single and two-stage jibs
- Multi-part load blocks
- Main winch with 2 speed motor
- Auxiliary winch
- ▶ Rotation-resistant load line
- Heavy duty wood flatbeds
- Extra heavy duty wood flatbeds
  Extra heavy duty steel flatbeds
- · Radio remote controls
- One-man or two-man baskets

- Self-leveling work platform
- Winch drum tensioner
- Continuous rotation
- Oil cooler
- Single front bumper outrigger (required for 370° or continuous rotation)
- Hydraulic hose reel
- Hydraulic auxiliary tool circuit
- ► Tool Box

#### Bigge Crane and Rigging Co.

10700 Bigge Avenue San Leandro, CA 94577

Phone: (888) 337-BIGGE or (510) 638-8100

Fax: (510) 639-4053 Email: info@bigge.com Web site: www.bigge.com